ELECTRICITY COMPANY OF GHANA LTD.
HEAD OFFICE - ELECTRO-VOLTA HOUSE
OFFICE OF THE MANAGING DIRECTOR

P. O. Box GP 521
Accra Ghana
+233 0 302 676 762
ecgho@ecggh.com
GA-145-7445

Our Ref: **MD/ MEGT/2025/V.1/083** Your Ref:

6 October 2025

The Honourable Minister
Ministry of Energy & Green Transition
P. O. Box SD 40
Stadium, Accra
Digital Address: GA-107-2970

Dear Sir,

Request for Answers to Parliamentary Question – Urgent

Reference is made to a letter from the Ministry of Energy and Green Transition, dated 3rd October 2025, with reference number SCR/ZA.281/281/01C (copy attached). Please find below ECG's responses.

"Question No. * 37 Mr Ohene Kwame Frimpong (Asante Akim North): To ask the Minister for Energy and Green Transition the cause of the intermittent power outages and the low voltage experienced by the people of Asante Akim North.

Answer

The Juansa feeder, which serves Asante Akim North under the ECG Konongo District, originates from the Konongo primary substation. Between 1st April and 30th September 2025, the feeder recorded:

- Three (3) unplanned outages
- Five (5) planned outages, broken down as follows:
  - Two (2) due to ECG Emergency Load Shedding
  - One (1) due to GRIDCo Load Shedding
  - Two (2) for corrective maintenance

Additionally, Voltage Improvement Technology (VIT) installations have been deployed on the feeder.

The Juansa feeder spans approximately 234.5 circuit kilometres. Its extended length has resulted in low voltage conditions for customers located at the tail end of the line. Network studies conducted on the feeder indicate that injecting a primary substation and creating outgoing feeders to segment the existing circuit will effectively resolve the voltage challenges.

To address this, ECG has initiated a project involving the construction of a 33kV network from the Kumawu substation to Agogo. The civil works on the substation are approximately 85% complete, while electromechanical works are expected to commence soon. The required equipment has arrived at the airport and is currently undergoing clearance procedures.

The route of the 33kV line to supply the substations passes through a forest reserve. ECG is actively engaging with the Forestry Commission to secure the necessary permits.

Question No. 541 Mr lssah Salifu Taylor (Tarkwa/Nsuaem)

To ask the Minister for Energy and Green Transition when will provide additional transformer to Tarkwa Nsuaem to replace the 33 damaged units due to overloaded transformers.

Answer

We acknowledge the existence of transformer overload challenges within the Agona District, which includes the Nsuaem community. These operational issues are primarily driven by evolving customer load patterns and broader economic activity. ECG typically addresses such challenges through the injection of transformers with appropriate ratings to stabilise supply and improve reliability.

While certain communities are experiencing overloads, we wish to clarify that there are currently no damaged transformers awaiting replacement in Nsuaem. The only faulty transformer within the district is located at Nkwanta. Affected customers have been temporarily transferred to adjacent healthy transformers to ensure continued service.

At present, 33kV-rated transformers required to relieve the overloaded units are unavailable. Consequently, localised load shedding is being implemented in Ningo and Subriso to manage the critically overloaded transformers in those areas.

We also wish to correct the assertion that 33 transformer units are damaged. This claim is inaccurate and does not reflect the current operational status.

Importantly, ECG is currently undergoing a procurement process to acquire and install 33kV transformers to address the overloads. The bid for this procurement was officially opened on Friday, 3rd October 2025, and the evaluation process is presently underway.

We trust this information will support the preparation of a comprehensive response to the Ministry and Parliament. Please advise if any further clarification is required.

Yours faithfully,

Kwame Kpekpena
Ag. Managing Director

Cc: DMD/E&O, ECG
Director of Operations, ECG